BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED SCHEDULE –'B'

Name of Work:- Improvements to roads and drains in ward 03 attur Yelahanka division

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	KSRRB: Excavation for road, drain and similar works KSRRB-300-1 Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift up to 0.5 mts, excavated surface levelled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH/Chapter 3 (P.No. 143, INo. 19.1)	Cum	1350.90	220.40	Rupees Two hunded twenty and paise forty only
2	KSSRB M2900-1: Plain Cement Concrete M 10 mix with crushed stone aggregate 40 mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications MORTH Specification No. 408 (P.No. 254 I.No. 34.1 of PW, P& IWTD S.R. 2018-19)	Cum	191.18	4479.56	Rupees Four thousand four hunded seventy nine and paise fifty six only
3	Providing and Laying Plain/reinforced cement concrete for side drain using M 20 Nominal Mix Concrete with OPC @ 300 Kgs. with 20 mm and sown size stone granite metal coarse aggregates @ 0.69 cum and fine aggregates 0.43 cum machine mixed, well compacted for walls and for bottom including centring, shuttering cost of materials HOM of machinary curing etc., complete excluding cost of steel as per MORTH specification No. 1500,1700, 2200 including cost of material, labour complete as per specification (P.No. 271,I.No. 37.59.2 of PW, P& IWTD S.R. 2018-19)	Cum	396.77	7070.20	Rupees Seven thousand seventy and paise twenty only

Executive Engineer-3
KRIDL, BBMP, Bangalore

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
4	KSRRB: M-2300:14 Providing TMT Steel reinforcement for RCC work Including straitening, cutting, bending, hooking, palcing in position lapping and or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (Laps, hooks, and wastage shall not be measured and paid) cost of materials, labours HOM of machinery complete as per specifications. MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (PNo. 239, I No. 29.29.2 of PW, P&IWTD S.R. 2018-19)	Tonne	24.67	73992.24	Rupees Seventy three thousand nine hundred ninety two and paise twenty four only
5	Providing and fixing of RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work lift charges curing and concrete finished surfaces on both sides etc., comlete as per drawing and the directions of Engineer in-charge (Date Rate)	Sqm	960.30	2337.00	Rupees two thousand three hundred thirty seven only
6	Providing and fixing of RCC precast cover slab of 250mm thick for drain in cement concrete 1:2:4 and jelly 20mm and down size with steel reinforcement, including form work lift charges curing and concrete finished surfaces on both sides etc., comlete as per drawing and the directions of Engineer in-charge (Date Rate)	Sqm	86.40	5418.00	Rupees five thousadn four hundred eighteen only

Signature of the Contractor

Executive Engineer-3
KRIDL, BBMP, Bangalore

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.